



# Primary-Single Phase Trenching Specifications



Phone: 1-888-581-8969  
Address: P.O. Box 688  
Dubois, PA 15801

## Sand bedding or use of conduit to be determined by UEC Engineer.

No more than 3 90° elbows in a single wire pull when in conduit. Not to exceed 270° of total bends.  
Ask UEC Engineer if there are questions.



## Notes:

1. It is the contractor's responsibility to notify PA-1-Call prior to any trenching or excavation.
2. Sand bedding of cable in the trench is required.
3. Contractor must supply and install 3" schedule-40 conduit with a pull rope under any roadway, driveway, sidewalk, patio, porch or anticipated future driveway.
4. Backfilling according to the specification is required prior to energizing the line. This will be done while United Electric Crew is on-site.
5. Contractor is responsible for properly backfilling the trench to prevent settling below original land contour or will be responsible to return to backfill the trench after ditch settles.
6. DO NOT use limestone or high calcium dust/stone.